

解：1) 明钟周期应为最长的一个阶段执行时间加延时

$$\therefore T_{\text{pipe}} = 2ns + 0.1ns = 2.1ns$$

$$2) S = \frac{T_{\text{pipe}}}{T_{\text{cycle}}} \times \frac{CPL_{\text{pipe}}}{CPL_{\text{cycle}}} = \frac{2.1}{7} \times \frac{N+5-1}{N} = 0.3 \frac{N+4}{N}$$

$$3) T_{\text{pipe}} \approx \frac{7}{k} + 0.1$$

$$\therefore S = \frac{T_{\text{pipe}}}{T_{\text{cycle}}} \times \frac{CPL_{\text{pipe}}}{CPL_{\text{cycle}}} = \frac{\frac{7}{k} + 0.1}{7} \times \frac{N+k-1}{N}$$

$$\lim_{\substack{N \rightarrow \infty \\ k \rightarrow \infty}} S = \lim_{\substack{N \rightarrow \infty \\ k \rightarrow \infty}} \frac{\frac{7}{k} + 0.1}{7} \times \frac{N+k-1}{N} = \frac{1}{35}$$

∴ 获得 35 倍加速。